BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 Indent No.20428

SCHEDULE-B

NAME OF WORK: Providing pothole filling at ward no.13, Shetty halli sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor G N RAMESH		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specfication & as per direction of Engineer-in-charge	Cum	148.78	79.0	Rupees Seventy Nine Only	11753.62
2	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam Specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired densitycomplete as per specfication & as per direction of Engineer-in-charge	Cum	115.85	1628.26	Rupees One Thousand Six Hundred Twenty Eight and Twenty Six Paise Only	188633.92
3	Filling Pot-Holes and patch repairs with Bituminous Concrete, 40mm., KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specfication & as per direction of Engineer-in-charge	Sqm	747.3	351.92	Rupees Three Hundred Fifty One and Ninety Two Paise Only	262989.82
4	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading complete as per specfication & as per direction of Engineer-in-charge	Cum	148.78	69.07	Rupees Sixty Nine and Seven Paise Only	10276.23
					Total	473653.59
					Percentage	-5.00%

Signature of the Contractor

Signature of the Contractor

Executive Engineer,
Dasarahalli Division

Executive Engineer